

- 1. THE CONCRETE COLLAR SHALL BE REINFORCED WITH #4 BARS AS SHOWN. THE CONCRETE SHALL EXTEND TO EDGE OF SAW CUT PAVEMENT EDGE.
- 2. REBAR WILL BE PLACED IN TWO LAYERS. FIRST LAYER (1/3 T) FROM TOP OF COLLAR AND SECOND LAYER (2/3 T) FROM TOP OF COLLAR. IF (T) IS 12" OR LESS ONE LAYER OF REBAR WILL BE USED, PLACED MID POINT BETWEEN TOP AND BOTTOM OF COLLAR.
- 3. REQUIREMENTS FOR NEW MANHOLE CONSTRUCTION AND MINOR MANHOLE ADJUSTMENTS IN NEW RECONSTRUCTION AND REAPING PROJECTS ARE INCLUDED IN DETAIL NO. 506S—3—SM, 506S—8—SM, 506S—8A—SM AND 506S—10—SM.
- 4. REFER TO TRENCH DETAIL FOR ADDITIONAL BACKFILL REQUIREMENTS WITH APPROPRIATE CONDITIONS.

REFERENCES DETAIL 506S-4-SM

The City of San Marcos Engineering and Capital Improvements	CURRENT AS OF 1/1/2021	Concrete Riser Collar	
RECORDED COPY SIGNED BY	2-15-2015	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD	1100S-1-SM
LAURIE MOYER, P.E.	ADOPTED		N.T.S. STANDARD DETAIL